



# ADDENDUM

Project:	RTN Water Infiltration Investigation	Addendum No.: 1
		1 Pages
		May 9, 2019
		820973-0080 (1.0)

The following change(s) in the RFP Documents are effective immediately.  
This Addendum forms part of the RFP Documents.

ITEM	DESCRIPTION	ACTION
<b>1.1</b>	<b>Clarification Questions</b>	
<b>1.1.1</b>	<p><b>Q1:</b> What are the approximate (anticipated) depths and locations of the boreholes to be drilled?</p> <p><b>A1:</b> Boreholes are to be drilled 10m deep or 2m into bedrock, whichever occurs first. The locations will be determined by the contractor with the assistance of the City in and around the Road to Nowhere Subdivision located to the East of the water treatment plant.</p>	
<b>1.1.2</b>	<p><b>Q2:</b> Confirmation whether groundwater testing is to be performed in-field, in an accredited laboratory, or both to confirm the presence and quantity of chlorine and fluoride.</p> <p><b>A2:</b> Ground water testing to be performed in the field.</p>	
	Colliers Project Leaders Inc.	Date: May 9, 2019
	Distribution: All Bidders	